











Peinemann Kranen B.V.



- Peinemann Kranen B.V. established in 1975 as part of Peinemann Mobilift Group B.V.
- 132 FTE, 98 FTE operational and 34 FTE staff employees
- Modern (fleet) crane and transport equipment, approx. 90 units
- Approx. 80% of crane rental activities in (petro)chemical industry
- Other 20% of rental activities related to harbour, heavy industry, wind industry or civil works







Planned lift operation – animation – movie images PEINE











Incident lift operation – movie images - animation

















Crisis Team consists of:

- Insurance specialists for major disasters (COT AON)
- Traumatic psychologists for the mental help
- Administrative law lawyers
- Insurance lawyers
- Damage experts









Investigation bodies/institutions



- I -SZW (Labor Inspection)
- OVV (Onderzoeksraad voor de Veiligheid)
- Aboma/ Eurorigging (Peinemann internal incident investigation)







Reason for internal investigation by Aboma / Eurorigging.



- To prevent incidents like this in the future
- To learn from this incident for the future
- To inform the stakeholders about the lessons learn:
 - management measures taken
 - management measures still to be taken









Missing / Failing safety/ quality barriers



- Peinemann ask Aboma to investigate this incident and investigate the root causes.
- During investigation one main cause could be identified and some contribution factors.
- Incident was caused by missing or failing barriers in the process
- Some missing or failing barriers were input in the organization improvements and the critical missing/ failing barriers were direct implemented.










Use method by ABOMA/Eurorigging



- Preliminary investigation (Looking for actual information)
- Determine scenarios, Collecting data at incident location
- Interview stakeholders and employees













Frameworks



- Legal framework
- Sector framework (Dutch Branch Organization VVT)
- Organizational framework (HSEQ Policy & Manual Peinemann)









Conclusion Aboma / Eurorigging



- Insufficient initial stability Lastdrager 24 (barge 400 tons crane)
- Insufficient founding ability, in combination with free hanging load and influence of wind
- Combination pontoon, crane and free fluid surfaces
- Failing barriers in implementation and work preparation.










Missing / Failing barriers

ABOMA incident report
















BowTie model – Barriers

PEINEMANN

(Calculation check was missing B2)





PEINEMANN.NL








BowTie model – Barriers

(Last check was missing B1)







PEINEMANN.NL





Safety management measures



B1-1 **Roles & Responsibilities**

- Review roles, responsibilities and compentences - SAFETY FOCUS
- Escalation model, lifting plan control procedure and Risk **Assessment**

B1-2

- Review and rewrite HSEQ **Peinemann Management**
- GO/NO GO implementation
- Work instructions Branch

B1-3

- Safety Culture Measurement
- 6 eyses control principle critical lifts
- Safety Behaviour Leadership training
- Enforcement and remuneration policy

B1-4

- Format request
 - subcontracting
 - Management of Change



B1-5

- Escalation model, lifting plan
- Gominal of Work form

B1-6

- Expansion staff
- Re positioning Engineering
- Workload determination





Compliance – Management of Change/ Management System



More focus on Quality -> More internal audits

An independent assessment done by Aboma (2 x a year)









Safety



• "If you think safety is expensive, try having an accident"

No blaming and shaming! Just learn from each other







